

ページ	正	誤																																																																																																																																																																								
228	<p>5. 単価表</p> <p>プレキャスト擁壁工 1m 当り単価表</p> <p>施工単価構成内訳 10m 当り算出</p> <table border="1" data-bbox="219 435 1144 1150"> <thead> <tr> <th>名称</th> <th>規格</th> <th>数量</th> <th>単位</th> <th>単価</th> <th>備考</th> </tr> </thead> <tbody> <tr> <td>(1) 世話役</td> <td></td> <td>1×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(2) ブロック工</td> <td></td> <td>1×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(3) 普通作業員</td> <td></td> <td>3×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(4) プレキャスト擁壁 ブロック</td> <td></td> <td>5</td> <td>個</td> <td></td> <td></td> </tr> <tr> <td>(5) バックホウ (クレーン機能付) 運転</td> <td>排出ガス対策型 (第 2 次基準値) クローラ型山積 0.8m³ (平積 0.6m³) 2.9 t 吊</td> <td>1×1.45×10/D</td> <td>日</td> <td></td> <td></td> </tr> <tr> <td>(5) ラフテレーンクレーン 賃料</td> <td>排出ガス対策型 (第 2 次基準値) 油圧伸縮ジブ型 25 t 吊</td> <td>1×10/D</td> <td>日</td> <td>略</td> <td>略</td> </tr> <tr> <td>(6) 運転手 (特殊)</td> <td></td> <td>1×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(7) 軽油</td> <td></td> <td>76×10/D</td> <td>ℓ</td> <td></td> <td></td> </tr> <tr> <td>(8) 雑工種 (基礎砕石)</td> <td></td> <td>表 4.3/100</td> <td></td> <td></td> <td></td> </tr> <tr> <td>(9) 雑工種 (均しコンクリート)</td> <td></td> <td>表 4.3/100</td> <td></td> <td></td> <td></td> </tr> <tr> <td>(10) 諸雑費</td> <td></td> <td>表 4.4/100</td> <td></td> <td></td> <td></td> </tr> <tr> <td>(11) 合計</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>(12) 単価</td> <td></td> <td>1.0</td> <td>m</td> <td></td> <td></td> </tr> </tbody> </table> <p>【訂正箇所】</p> <ul style="list-style-type: none"> ・ (5)バックホウ (クレーン機能付) 運転 数量「1×10/D」を「1×1.45×10/D」に訂正する。 	名称	規格	数量	単位	単価	備考	(1) 世話役		1×10/D	人			(2) ブロック工		1×10/D	人			(3) 普通作業員		3×10/D	人			(4) プレキャスト擁壁 ブロック		5	個			(5) バックホウ (クレーン機能付) 運転	排出ガス対策型 (第 2 次基準値) クローラ型山積 0.8m ³ (平積 0.6m ³) 2.9 t 吊	1×1.45×10/D	日			(5) ラフテレーンクレーン 賃料	排出ガス対策型 (第 2 次基準値) 油圧伸縮ジブ型 25 t 吊	1×10/D	日	略	略	(6) 運転手 (特殊)		1×10/D	人			(7) 軽油		76×10/D	ℓ			(8) 雑工種 (基礎砕石)		表 4.3/100				(9) 雑工種 (均しコンクリート)		表 4.3/100				(10) 諸雑費		表 4.4/100				(11) 合計						(12) 単価		1.0	m			<p>5. 単価表</p> <p>プレキャスト擁壁工 1m 当り単価表</p> <p>施工単価構成内訳 10m 当り算出</p> <table border="1" data-bbox="1193 435 2119 1150"> <thead> <tr> <th>名称</th> <th>規格</th> <th>数量</th> <th>単位</th> <th>単価</th> <th>備考</th> </tr> </thead> <tbody> <tr> <td>(1) 世話役</td> <td></td> <td>1×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(2) ブロック工</td> <td></td> <td>1×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(3) 普通作業員</td> <td></td> <td>3×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(4) プレキャスト擁壁 ブロック</td> <td></td> <td>5</td> <td>個</td> <td></td> <td></td> </tr> <tr> <td>(5) バックホウ (クレーン機能付) 運転</td> <td>排出ガス対策型 (第 2 次基準値) クローラ型山積 0.8m³ (平積 0.6m³) 2.9 t 吊</td> <td>1×10/D</td> <td>日</td> <td></td> <td></td> </tr> <tr> <td>(5) ラフテレーンクレーン 賃料</td> <td>排出ガス対策型 (第 2 次基準値) 油圧伸縮ジブ型 25 t 吊</td> <td>1×10/D</td> <td>日</td> <td>略</td> <td>略</td> </tr> <tr> <td>(6) 運転手 (特殊)</td> <td></td> <td>1×10/D</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(7) 軽油</td> <td></td> <td>76×10/D</td> <td>ℓ</td> <td></td> <td></td> </tr> <tr> <td>(8) 雑工種 (基礎砕石)</td> <td></td> <td>表 4.3/100</td> <td></td> <td></td> <td></td> </tr> <tr> <td>(9) 雑工種 (均しコンクリート)</td> <td></td> <td>表 4.3/100</td> <td></td> <td></td> <td></td> </tr> <tr> <td>(10) 諸雑費</td> <td></td> <td>表 4.4/100</td> <td></td> <td></td> <td></td> </tr> <tr> <td>(11) 合計</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>(12) 単価</td> <td></td> <td>1.0</td> <td>m</td> <td></td> <td></td> </tr> </tbody> </table>	名称	規格	数量	単位	単価	備考	(1) 世話役		1×10/D	人			(2) ブロック工		1×10/D	人			(3) 普通作業員		3×10/D	人			(4) プレキャスト擁壁 ブロック		5	個			(5) バックホウ (クレーン機能付) 運転	排出ガス対策型 (第 2 次基準値) クローラ型山積 0.8m ³ (平積 0.6m ³) 2.9 t 吊	1×10/D	日			(5) ラフテレーンクレーン 賃料	排出ガス対策型 (第 2 次基準値) 油圧伸縮ジブ型 25 t 吊	1×10/D	日	略	略	(6) 運転手 (特殊)		1×10/D	人			(7) 軽油		76×10/D	ℓ			(8) 雑工種 (基礎砕石)		表 4.3/100				(9) 雑工種 (均しコンクリート)		表 4.3/100				(10) 諸雑費		表 4.4/100				(11) 合計						(12) 単価		1.0	m		
名称	規格	数量	単位	単価	備考																																																																																																																																																																					
(1) 世話役		1×10/D	人																																																																																																																																																																							
(2) ブロック工		1×10/D	人																																																																																																																																																																							
(3) 普通作業員		3×10/D	人																																																																																																																																																																							
(4) プレキャスト擁壁 ブロック		5	個																																																																																																																																																																							
(5) バックホウ (クレーン機能付) 運転	排出ガス対策型 (第 2 次基準値) クローラ型山積 0.8m ³ (平積 0.6m ³) 2.9 t 吊	1×1.45×10/D	日																																																																																																																																																																							
(5) ラフテレーンクレーン 賃料	排出ガス対策型 (第 2 次基準値) 油圧伸縮ジブ型 25 t 吊	1×10/D	日	略	略																																																																																																																																																																					
(6) 運転手 (特殊)		1×10/D	人																																																																																																																																																																							
(7) 軽油		76×10/D	ℓ																																																																																																																																																																							
(8) 雑工種 (基礎砕石)		表 4.3/100																																																																																																																																																																								
(9) 雑工種 (均しコンクリート)		表 4.3/100																																																																																																																																																																								
(10) 諸雑費		表 4.4/100																																																																																																																																																																								
(11) 合計																																																																																																																																																																										
(12) 単価		1.0	m																																																																																																																																																																							
名称	規格	数量	単位	単価	備考																																																																																																																																																																					
(1) 世話役		1×10/D	人																																																																																																																																																																							
(2) ブロック工		1×10/D	人																																																																																																																																																																							
(3) 普通作業員		3×10/D	人																																																																																																																																																																							
(4) プレキャスト擁壁 ブロック		5	個																																																																																																																																																																							
(5) バックホウ (クレーン機能付) 運転	排出ガス対策型 (第 2 次基準値) クローラ型山積 0.8m ³ (平積 0.6m ³) 2.9 t 吊	1×10/D	日																																																																																																																																																																							
(5) ラフテレーンクレーン 賃料	排出ガス対策型 (第 2 次基準値) 油圧伸縮ジブ型 25 t 吊	1×10/D	日	略	略																																																																																																																																																																					
(6) 運転手 (特殊)		1×10/D	人																																																																																																																																																																							
(7) 軽油		76×10/D	ℓ																																																																																																																																																																							
(8) 雑工種 (基礎砕石)		表 4.3/100																																																																																																																																																																								
(9) 雑工種 (均しコンクリート)		表 4.3/100																																																																																																																																																																								
(10) 諸雑費		表 4.4/100																																																																																																																																																																								
(11) 合計																																																																																																																																																																										
(12) 単価		1.0	m																																																																																																																																																																							

ページ	正	誤																																																																																																																																																												
595	<p>2-1-6 単価表 防雪柵設置及び撤去 1m 当り単価表 施工単価構成内訳</p> <p style="text-align: right;">1 日（Lm）当り算出</p> <table border="1" data-bbox="197 419 1151 991"> <thead> <tr> <th>名 称</th> <th>規 格</th> <th>数 量</th> <th>単 位</th> <th>単 価</th> <th>備 考</th> </tr> </thead> <tbody> <tr> <td>(1) 世 話 役</td> <td></td> <td>表 2.2</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(2) 普 通 作 業 員</td> <td></td> <td>表 2.2</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(3) 防 雪 柵 吹 溜 式</td> <td>仮設式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(3) 防 雪 柵 吹 溜 式</td> <td>固定式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(3) 防 雪 柵 吹 払 式</td> <td>仮設式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(3) 防 雪 柵 吹 払 式</td> <td>固定式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(4) 運 転 手（特 殊）</td> <td></td> <td>0.7</td> <td>人</td> <td></td> <td>表 2.5</td> </tr> <tr> <td>(5) 軽 油</td> <td></td> <td>18</td> <td>ℓ</td> <td></td> <td>表 2.5</td> </tr> <tr> <td>(6) ト ラ ッ ク （クレーン装置付）</td> <td>4 t 級 2.9 t 吊</td> <td>1.06</td> <td>供用日</td> <td>機損 1-1 (P. 104)</td> <td>表 2.5</td> </tr> <tr> <td>(7) 諸 雑 費</td> <td></td> <td>表 2.4/100</td> <td></td> <td>Σ (1)～ (6) - (3)</td> <td></td> </tr> <tr> <td>(8) 合 計</td> <td></td> <td></td> <td></td> <td></td> <td>Σ (1)～(7)</td> </tr> <tr> <td>(9) 単 価</td> <td></td> <td>1.0</td> <td>m</td> <td></td> <td>(8)/L</td> </tr> </tbody> </table> <p>【訂正箇所】</p> <ul style="list-style-type: none"> ・ (4) 運転手（特殊）、(5) 軽油、(6) トラック（クレーン装置付）の備考欄の「固定式の時」を削除する。 	名 称	規 格	数 量	単 位	単 価	備 考	(1) 世 話 役		表 2.2	人			(2) 普 通 作 業 員		表 2.2	人			(3) 防 雪 柵 吹 溜 式	仮設式	表 2.3	m		請負者購入の時	(3) 防 雪 柵 吹 溜 式	固定式	表 2.3	m		請負者購入の時	(3) 防 雪 柵 吹 払 式	仮設式	表 2.3	m		請負者購入の時	(3) 防 雪 柵 吹 払 式	固定式	表 2.3	m		請負者購入の時	(4) 運 転 手（特 殊）		0.7	人		表 2.5	(5) 軽 油		18	ℓ		表 2.5	(6) ト ラ ッ ク （クレーン装置付）	4 t 級 2.9 t 吊	1.06	供用日	機損 1-1 (P. 104)	表 2.5	(7) 諸 雑 費		表 2.4/100		Σ (1)～ (6) - (3)		(8) 合 計					Σ (1)～(7)	(9) 単 価		1.0	m		(8)/L	<p>2-1-6 単価表 防雪柵設置及び撤去 1m 当り単価表 施工単価構成内訳</p> <p style="text-align: right;">1 日（Lm）当り算出</p> <table border="1" data-bbox="1182 419 2136 991"> <thead> <tr> <th>名 称</th> <th>規 格</th> <th>数 量</th> <th>単 位</th> <th>単 価</th> <th>備 考</th> </tr> </thead> <tbody> <tr> <td>(1) 世 話 役</td> <td></td> <td>表 2.2</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(2) 普 通 作 業 員</td> <td></td> <td>表 2.2</td> <td>人</td> <td></td> <td></td> </tr> <tr> <td>(3) 防 雪 柵 吹 溜 式</td> <td>仮設式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(3) 防 雪 柵 吹 溜 式</td> <td>固定式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(3) 防 雪 柵 吹 払 式</td> <td>仮設式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(3) 防 雪 柵 吹 払 式</td> <td>固定式</td> <td>表 2.3</td> <td>m</td> <td></td> <td>請負者購入の時</td> </tr> <tr> <td>(4) 運 転 手（特 殊）</td> <td></td> <td>0.7</td> <td>人</td> <td></td> <td>固定式の時 表 2.5</td> </tr> <tr> <td>(5) 軽 油</td> <td></td> <td>18</td> <td>ℓ</td> <td></td> <td>固定式の時 表 2.5</td> </tr> <tr> <td>(6) ト ラ ッ ク （クレーン装置付）</td> <td>4 t 級 2.9 t 吊</td> <td>1.06</td> <td>供用日</td> <td>機損 1-1 (P. 104)</td> <td>固定式の時 表 2.5</td> </tr> <tr> <td>(7) 諸 雑 費</td> <td></td> <td>表 2.4/100</td> <td></td> <td>Σ (1)～ (6) - (3)</td> <td></td> </tr> <tr> <td>(8) 合 計</td> <td></td> <td></td> <td></td> <td></td> <td>Σ (1)～(7)</td> </tr> <tr> <td>(9) 単 価</td> <td></td> <td>1.0</td> <td>m</td> <td></td> <td>(8)/L</td> </tr> </tbody> </table>	名 称	規 格	数 量	単 位	単 価	備 考	(1) 世 話 役		表 2.2	人			(2) 普 通 作 業 員		表 2.2	人			(3) 防 雪 柵 吹 溜 式	仮設式	表 2.3	m		請負者購入の時	(3) 防 雪 柵 吹 溜 式	固定式	表 2.3	m		請負者購入の時	(3) 防 雪 柵 吹 払 式	仮設式	表 2.3	m		請負者購入の時	(3) 防 雪 柵 吹 払 式	固定式	表 2.3	m		請負者購入の時	(4) 運 転 手（特 殊）		0.7	人		固定式の時 表 2.5	(5) 軽 油		18	ℓ		固定式の時 表 2.5	(6) ト ラ ッ ク （クレーン装置付）	4 t 級 2.9 t 吊	1.06	供用日	機損 1-1 (P. 104)	固定式の時 表 2.5	(7) 諸 雑 費		表 2.4/100		Σ (1)～ (6) - (3)		(8) 合 計					Σ (1)～(7)	(9) 単 価		1.0	m		(8)/L
名 称	規 格	数 量	単 位	単 価	備 考																																																																																																																																																									
(1) 世 話 役		表 2.2	人																																																																																																																																																											
(2) 普 通 作 業 員		表 2.2	人																																																																																																																																																											
(3) 防 雪 柵 吹 溜 式	仮設式	表 2.3	m		請負者購入の時																																																																																																																																																									
(3) 防 雪 柵 吹 溜 式	固定式	表 2.3	m		請負者購入の時																																																																																																																																																									
(3) 防 雪 柵 吹 払 式	仮設式	表 2.3	m		請負者購入の時																																																																																																																																																									
(3) 防 雪 柵 吹 払 式	固定式	表 2.3	m		請負者購入の時																																																																																																																																																									
(4) 運 転 手（特 殊）		0.7	人		表 2.5																																																																																																																																																									
(5) 軽 油		18	ℓ		表 2.5																																																																																																																																																									
(6) ト ラ ッ ク （クレーン装置付）	4 t 級 2.9 t 吊	1.06	供用日	機損 1-1 (P. 104)	表 2.5																																																																																																																																																									
(7) 諸 雑 費		表 2.4/100		Σ (1)～ (6) - (3)																																																																																																																																																										
(8) 合 計					Σ (1)～(7)																																																																																																																																																									
(9) 単 価		1.0	m		(8)/L																																																																																																																																																									
名 称	規 格	数 量	単 位	単 価	備 考																																																																																																																																																									
(1) 世 話 役		表 2.2	人																																																																																																																																																											
(2) 普 通 作 業 員		表 2.2	人																																																																																																																																																											
(3) 防 雪 柵 吹 溜 式	仮設式	表 2.3	m		請負者購入の時																																																																																																																																																									
(3) 防 雪 柵 吹 溜 式	固定式	表 2.3	m		請負者購入の時																																																																																																																																																									
(3) 防 雪 柵 吹 払 式	仮設式	表 2.3	m		請負者購入の時																																																																																																																																																									
(3) 防 雪 柵 吹 払 式	固定式	表 2.3	m		請負者購入の時																																																																																																																																																									
(4) 運 転 手（特 殊）		0.7	人		固定式の時 表 2.5																																																																																																																																																									
(5) 軽 油		18	ℓ		固定式の時 表 2.5																																																																																																																																																									
(6) ト ラ ッ ク （クレーン装置付）	4 t 級 2.9 t 吊	1.06	供用日	機損 1-1 (P. 104)	固定式の時 表 2.5																																																																																																																																																									
(7) 諸 雑 費		表 2.4/100		Σ (1)～ (6) - (3)																																																																																																																																																										
(8) 合 計					Σ (1)～(7)																																																																																																																																																									
(9) 単 価		1.0	m		(8)/L																																																																																																																																																									

ページ	正	誤																																																																														
812	<p>⑬ 仮橋・仮栈橋工</p> <p>5-3 高欄設置・撤去工1m当り単価表</p> <p>表5.4 高欄型式、施工区分による歩掛(100m当り)</p> <table border="1" data-bbox="219 587 1084 951"> <thead> <tr> <th>高欄型式</th> <th>施工区分</th> <th>世話役(人)</th> <th>普通作業員(人)</th> <th>日当り作業量(m/日)</th> </tr> </thead> <tbody> <tr> <td rowspan="4">単管パイプ型</td> <td>設置</td> <td>1.0</td> <td>3.8</td> <td><u>41</u></td> </tr> <tr> <td>設置～損料</td> <td>1.0</td> <td>3.8</td> <td><u>41</u></td> </tr> <tr> <td>損料～撤去</td> <td>0.6</td> <td>2.1</td> <td><u>78</u></td> </tr> <tr> <td>撤去</td> <td>0.6</td> <td>2.1</td> <td><u>78</u></td> </tr> <tr> <td rowspan="4">ガードレール型</td> <td>設置</td> <td>1.3</td> <td>5.0</td> <td><u>36</u></td> </tr> <tr> <td>設置～損料</td> <td>1.3</td> <td>5.0</td> <td><u>36</u></td> </tr> <tr> <td>損料～撤去</td> <td>0.7</td> <td>3.3</td> <td><u>52</u></td> </tr> <tr> <td>撤去</td> <td>0.7</td> <td>3.3</td> <td><u>52</u></td> </tr> </tbody> </table> <p>【訂正箇所】</p> <ul style="list-style-type: none"> ・日当り作業量(m/日)を訂正する。(単管パイプ型とガードレール型を入れ替える。) 	高欄型式	施工区分	世話役(人)	普通作業員(人)	日当り作業量(m/日)	単管パイプ型	設置	1.0	3.8	<u>41</u>	設置～損料	1.0	3.8	<u>41</u>	損料～撤去	0.6	2.1	<u>78</u>	撤去	0.6	2.1	<u>78</u>	ガードレール型	設置	1.3	5.0	<u>36</u>	設置～損料	1.3	5.0	<u>36</u>	損料～撤去	0.7	3.3	<u>52</u>	撤去	0.7	3.3	<u>52</u>	<p>⑬ 仮橋・仮栈橋工</p> <p>5-3 高欄設置・撤去工1m当り単価表</p> <p>表5.4 高欄型式、施工区分による歩掛(100m当り)</p> <table border="1" data-bbox="1151 587 2011 951"> <thead> <tr> <th>高欄型式</th> <th>施工区分</th> <th>世話役(人)</th> <th>普通作業員(人)</th> <th>日当り作業量(m/日)</th> </tr> </thead> <tbody> <tr> <td rowspan="4">単管パイプ型</td> <td>設置</td> <td>1.0</td> <td>3.8</td> <td><u>36</u></td> </tr> <tr> <td>設置～損料</td> <td>1.0</td> <td>3.8</td> <td><u>36</u></td> </tr> <tr> <td>損料～撤去</td> <td>0.6</td> <td>2.1</td> <td><u>52</u></td> </tr> <tr> <td>撤去</td> <td>0.6</td> <td>2.1</td> <td><u>52</u></td> </tr> <tr> <td rowspan="4">ガードレール型</td> <td>設置</td> <td>1.3</td> <td>5.0</td> <td><u>41</u></td> </tr> <tr> <td>設置～損料</td> <td>1.3</td> <td>5.0</td> <td><u>41</u></td> </tr> <tr> <td>損料～撤去</td> <td>0.7</td> <td>3.3</td> <td><u>78</u></td> </tr> <tr> <td>撤去</td> <td>0.7</td> <td>3.3</td> <td><u>78</u></td> </tr> </tbody> </table>	高欄型式	施工区分	世話役(人)	普通作業員(人)	日当り作業量(m/日)	単管パイプ型	設置	1.0	3.8	<u>36</u>	設置～損料	1.0	3.8	<u>36</u>	損料～撤去	0.6	2.1	<u>52</u>	撤去	0.6	2.1	<u>52</u>	ガードレール型	設置	1.3	5.0	<u>41</u>	設置～損料	1.3	5.0	<u>41</u>	損料～撤去	0.7	3.3	<u>78</u>	撤去	0.7	3.3	<u>78</u>
高欄型式	施工区分	世話役(人)	普通作業員(人)	日当り作業量(m/日)																																																																												
単管パイプ型	設置	1.0	3.8	<u>41</u>																																																																												
	設置～損料	1.0	3.8	<u>41</u>																																																																												
	損料～撤去	0.6	2.1	<u>78</u>																																																																												
	撤去	0.6	2.1	<u>78</u>																																																																												
ガードレール型	設置	1.3	5.0	<u>36</u>																																																																												
	設置～損料	1.3	5.0	<u>36</u>																																																																												
	損料～撤去	0.7	3.3	<u>52</u>																																																																												
	撤去	0.7	3.3	<u>52</u>																																																																												
高欄型式	施工区分	世話役(人)	普通作業員(人)	日当り作業量(m/日)																																																																												
単管パイプ型	設置	1.0	3.8	<u>36</u>																																																																												
	設置～損料	1.0	3.8	<u>36</u>																																																																												
	損料～撤去	0.6	2.1	<u>52</u>																																																																												
	撤去	0.6	2.1	<u>52</u>																																																																												
ガードレール型	設置	1.3	5.0	<u>41</u>																																																																												
	設置～損料	1.3	5.0	<u>41</u>																																																																												
	損料～撤去	0.7	3.3	<u>78</u>																																																																												
	撤去	0.7	3.3	<u>78</u>																																																																												